

91-168 Removal and installation of armrest with lifting mechanism on driver's seat (coupe)

Note

Modified armrests on the driver's seat were phased in starting in September 1990. When the driver's seat backrest is tilted forward a mechanism in the seat backrest frame lifts the modified armrest slightly from its horizontal position. This prevents it from hitting against the shift lever or the switches for the power windows. The modified armrest, identifiable by the extending shaft on the mounting flange, can only be bolted to backrest frames with lifting mechanism.






Removal, installation

- Press cover off above mounting flange and screw off the two nuts (arrows).
- 2 Remove armrest (1) from backrest frame.

37-1327

Reinstall in opposite order. Observe installation note!



P91.10-0249-01

Installation note

In order to avoid damage to the lifting mechanism in the backrest frame ensure that the modified armrest is bolted on only with the backrest arrested in the upright position.

